

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division

B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

APPROVED TENDER SCHEDULE -'B'

Item No: 38

Name of Work:-Developmental works near Vivekananda park Yelahanka 4th phase & SFS 707 in Attur ward No:03 Yelahanka New Town Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Approved Rates Sn G VENKATE GOWDA	Rate in Words
1	KSRRB M200-15.2 : Dismantling of existing structures like culverts, bridges retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work including T & P and scaffolding wherever necessary sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres complete as per specification.iii) Dismantling Stone Masonry. B.Rubble Stone masonry in cement mortar (Page No.134, Item No. 18.27)	CMT	38.40	251.00	Rupees two hundred fifty one only
2	KSRRB M200-12.2: Dismantling of existing structures like culverts, bridges retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work including T & P and scaffolding wherever necessary sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres complete as per specification.i) Lime/Cement concrete. LBy Manual means : A. Lime/Cement Concrete, LBy Manual means : B cement concrete Grade M-15 & M-20 (Page No.133, Item No. 18.18)	CMT	19.20	383.00	Rupees three hundred eighty three only
3	KSRRB M2100-2.1 : Earth work in excavation for foundation of structures as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material complete as per specifications. B. Mechanical Means (i) Depth upto 3 m. MORTH Specification No.Section 304 (Page No.206, Item No. 27.4)	CMT	368.00	52.00	Rupees fifty two only
4	KSRRB 2.8 : Providing and Filling in foundation with granite/trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead upto 50m and lift of 1.5m complete as per specifications.Specification No.KBS (Page No.6, Item No. 2.15)	CMT	36.48	2175.00	Rupees two thousand one hundred seventy five only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Approved Rates SRI G VENKATE GOWDA	Rate in Words
5	KSRRB M2100-10 : Plain cement concrete M 10 with OPC cement @ 220 kgs with crushed 40mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications. MORTH Specification No.2100 (Page No.208, Item No. 27.18)	CMT	11.52	5805.00	Rupees five thousand eight hundred five only
6	KSRRB M2100-20.2 : Plain / Reinforced Cement concrete in open foundation with OPC cement design mix M35 @ 390 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.68 cum and fine aggregates @ 0.45 cum with superplasticiser @ 3lts confirming to IS 9103-1999 Reaffirmed-2010 complete as per drawing and technical specification. Case-II : With Batching Plant, Transit Mixer and Concrete Pump. MORTH Specification No.1500, 1700 & 2100 (Page No.210, Item No. 27.37)	CMT	43.52	6600.00	Rupees six thousand six hundred only
7	KSRRB M2200-5.18 : Design mix M 35 with OPC cement @ 390kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.68cum and fine aggregates @ 0.45 cum, with superplasticiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008 i) upto 5m height (Page No.214, Item No. 28.7.18)	CMT	28.80	7430.00	Rupees seven thousand four hundred thirty only
8	KSRRB M2300-8.1 : Furnishing and Placing Reinforced / Prestressed cement concrete in super-structure as per drawing and Technical Specification complete as per specifications. D/RCC/FSC with OPC cement design mix M35 @ 390kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.68cum and fine aggregates @ 0.45cum, with superplasticiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008. Case-II : Using Batching plant, Transit mixer & concrete pump Height upto 5m (Page No.223, Item No. 29.16.1)	CMT	32.04	7523.00	Rupees seven thousand five hundred twenty three only
9	KSRRB M2200-6: Supplying, fitting and placing TMT bar reinforcement in sub-structure as per drawing and Technical Specifications complete as per specifications. MORTH Specification No.1600 & 2200 (Page No.215, Item No. 28.8)	Mte	7.67	69143.00	Rupees sixty nine thousand one hundred forty three only
10	KSRRB M2300-14 : Supplying, fitting and placing TMT bar reinforcement in super-structure complete as per drawing and technical specifications complete as per specifications. MORTH specification No.1600 (Page No.231, Item No. 29.29)	Mte	3.92	70048.00	Rupees seventy thousand forty eight only
11	KSRRB M2200-8. Providing weep holes in brick masonry/ plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1v : 20H towards drawing face. Complete as per drawing and Technical Specification Complete as per specifications MORTH specifications No.2706 & 2200 (Page No.215, Item No. 28.10)	Nos/Rmt	60.00	181.00	Rupees one hundred eighty one only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Approved Rates Sri G VENKATE GOWDA	Rate in Words
13	Collecting, conveying and disposal of surplus / excavated earth to designated dumping site (15.00 kms) as directed by the Engineer in charge.	CMT	184.00	95.00	Rupees ninety five only
14	KSRRBM400-17, Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No.406(Item no20.18,Page no154,PWD SR 2015-16)	CMT	61.60	1714.00	Rupees one thousand seven hundred fourteen only
14	KSRRB M500-6, Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WBM, WMM including cleaning of road surface and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH Specifications No502 (ITEM NO21.6, Page no160, PWD SR 2015-16)	Sqm	308.00	33.00	Rupees thirty three only
15	KSRRB M500-19. Providing and laying bituminous concrete 40 mm thick with 40-60 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 to 5.6% of mix and filler, transporting the hot mix to work site, laying with Mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects as per specifications. MORTH Specification No. P.No 164	CMT	12.32	9823.00	Rupees nine thousand eight hundred twenty three only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-54.